

Quotation Advert

Opening Date: 2019-07-17

Closing Date: 2019-07-26

Closing Time: 11:00

INSTITUTION DETAILS

Institution Name: Benedictine hospital

Province: KwaZulu-Natal

Department or Entity: Department of Health

Division or section: Central Supply Chain Management

Place where goods / services is required maintenance

Date Submitted 2019-07-16

ITEM CATEGORY AND DETAILS

Quotation Number: ZNQ:
155 / 2019-20

Item Category: Services

Item Description: 1.REPLACEMENT OF SOAK WAY

CIBD WITH A GRADING OF 2GB ASMINIMIM REQUIREMENT

Quantity (If supplies)

COMPULSORY BRIEFING SESSION / SITE VISIT

Select Type: Both

Date : 2019-07-19

Time: 12H00

Venue: AT DENGENI CLINIC

QUOTES CAN BE COLLECTED FROM: DOCUMENT WILL BE AVAILABLE ON SITE METTING

QUOTES SHOULD BE DELIVERED TO: mangoba.mdladja@kznhealth.gov.za/to tender box next to PRO office

ENQUIRIES REGARDING THE ADVERT MAY BE DIRECTED TO:

Name: PHAKATHI A.A

Email: Hlengiwe.Mthembu@kznhealth.gov.za


Contact Number:

035 831 7062






Finance Manager Name:

Mdladla G.N.M

Finance Manager Signature:



No late quotes will be considered

 Submit  Save  Save As...  Close  Print Preview

 Print this page

Replacement of Septic tank for Dengeni Clinic/Benedictine hospital

SPECIFICATION

1. SCOPE OF CONTRACT

- These calls for the building/replacement of soak way.

2. REQUIREMENTS

- **NB:** The contractor to provide the Safety plan for digging of trenches in public. **(This safety plan will be considered as requirement on evaluation)**
- Only contractors registered on CIDB with a grading of 1GB as minimum requirement.
- The Contractor will be requested to visit the site to take all measurements necessary also be part of discussion.
- Contractors are also advised to be present on the site meeting for anything that might be discussed outside the specification.
- The competed workmen skilled in their trades shall carry out all work. **(provide proof)**
- Quality shall of the best standard practice and workmanship shall be subject to the approval of the Hospital Representative.
- During the progress of work the Contractor shall carefully clean up after his/her men and shall the area and the portion of the building clean and free from debris.
- The Contractor will be required to conform to the Security and other Regulations imposed by the Health Service Department and in addition are to provide suitable means of the identification of all workmen employed on his/her work to the approval of the Hospital.
- **NB:** Any damages occurred while construction working on site construction will be responsible.

- The Contractor is also advised to comply with Health and Safety Regulations while performing duties on the Hospital/clinic premises.

3. PROGRAMME

- Time is considered to this contract and the Contractors taking quotations are advised if necessary to discuss the program for the work with the Hospital Representative on Technical division before submitting the quotations.
- Contract period for this work shall be **3 weeks. NB.** The tenant will be using the building while the construction is on progress so the construction is advised to not disconnect the septic tank before finishing the building of the new one.
- **NB: The site is outside the clinic so the contractor will take full responsibility of his/her material and make sure that the stamping is done properly to prevent soil erosion since the site is sloping.**

4. QUOTATIONS

- Quotations for the entire work contained in this contract are to be submitted on the official quotation form provided, sealed in an envelope endorsed and will be deposited in a quotation box at the Hospital main entrance by the date and time stipulated on the official invitation form.

5. WORK TO BE DONE

BILL OF QUANTITIES

ITEM	DESCRIPTION	QTY	SUPPLY RATE	INSTALL RATE	SUB TOTAL
1.	Digging of new soak way 1.5m x 1.5m x 2.5m (The contractor is subjected to clean the site before staring any digging since it full of	6m ³			

	Guava trees)				
2.	Surround the working area with demarcating fence to prevent any unauthorised entry and animals during construction period and remove it after completion of work.	m ²			
3.	Connect the existing overflow pipes to soak way line sewer line with 110mm SABS approved UG PIPE	±90m			
4.	Agricultural pipe should be used inside the soak way. (all pipes should be laid on a bedding)	2m			
5.	110mm PVC socket	20			
6.	110mm Y-junctions	07			
7.	110mm x 45°PVC UG bends	07			
8.	110mm PVC UG pipes	17			
9.	80 Rough stones	2 tones			
10.	40 Rough stones NB. Soak way to covered with approved membrane	2 tones			
11.	River sand	4 tones			
12.	Membrane	100m			
22.	Allow for complying with the Project EPWP Specification	Item			
23.	Drawing is attached on the document				
	Total Amount				

