

## Quotation Advert

**Opening Date:** 2019-11-01

**Closing Date:** 2019-11-13

**Closing Time:** 11:00

### INSTITUTION DETAILS

**Institution Name:** Benedictine hospital

**Province:** KwaZulu-Natal

**Department or Entity:** Department of Health

**Division or section:** Central Supply Chain Management

**Place where goods / services is required** Maintenance

**Date Submitted** 2019-10-31

### ITEM CATEGORY AND DETAILS

**Quotation Number:** ZNQ:  
355 / 2019-20

**Item Category:** Services

**Item Description:**

1. Renovation of OPD passage and consulting rooms
  - wall painting
  - floor vinyl sheet on the passage
  - and replacement of miranti doors and door frames.

CIDB grading 2GB and above is allowed to tender

Specification attached

### Quantity (if supplies)

### COMPULSORY BRIEFING SESSION / SITE VISIT

**Select Type:** Both

**Date :** 2019-11-06

**Time:** 11H00

**Venue:** Sisters Lounge

**QUOTES CAN BE COLLECTED FROM:** Documents will only be available on briefing session

**QUOTES SHOULD BE DELIVERED TO:** TO BE DEPOSITED IN THE TENDER BOX NEXT TO PRO OFFICE

### ENQUIRIES REGARDING THE ADVERT MAY BE DIRECTED TO:

**Name:** Phakathi AA

**Email:** hlengiwe.mtheinbu@kznhealth.gov.za


**Contact Number:**

035 8317062

**Finance Manager Name:**






Mdladla GNM

**Finance Manager Signature:**



---

No late quotes will be considered

 Submit  Save  Save As...  Close  Print Preview

[Print this page](#)



**health**

Department:  
Health  
PROVINCE OF KWAZULU-NATAL



**OPD PASSAGE AND CONSULTING ROOMS WALL  
PAINTING AND FLOOR VINYL SHEET REPLACEMENT  
ON THE PASSAGE ALSO REPLACEMENT OF MIRANTI  
FRAME AND DOORS.**

## **(TECHNICAL SPECIFICATIONS)**

**Artisan Painter: B.M. MBATHA**

**Foreman : S.B. Dlamini (Hospital Foreman)**

**Institution : Benedictine Hospital**

## PROJECT SPECIFICATION

The work to be carried out in terms of this section of the project comprises the supply and installation of *all the materials necessary, as per the Schedule of Rates*

### PART 1

#### 1.1. SCOPE OF WORK

- 1.1.1 The contractor to prepare all identified walls and floor.
- 1.1.2 Painting of walls and doors.
- 1.1.3 Removing of existing damaged vinyl sheet floor.
- 1.1.4 Replacing of all cracked and missing window glasses.
- 1.1.5 Replacing of missing wall tiles in ablution.
- 1.1.6 Replacing of paraplegic toilet with basin and mirror.

## **OPD PASSAGE AND CONSULTING ROOMS WALL PAINTING AND FLOOR VINYL SHEET REPLACEMENT ON THE PASSAGE ALSO REPLACEMENT OF MIRANTI FRAME AND DOORS.**

### PART 2

#### 2.1 TECHNICAL SPECIFICATION

This TECHNICAL SPECIFICATION shall be read in conjunction with all other sections of the SPECIFICATION and cognisance shall be taken of the clauses relevant to these particular renovations, whether any specific clauses are referred to or not. **NB. Contract period for this work 10 weeks.**

### Part 3

#### 3.1 Requirements.

- 3.1.1. CIDB grading = 2GB plus
- 3.1.2. The contractor to submit Trade Test Certificate together with documents for the person who will monitor the work and will be onsite every day. (This will be considered on evaluation and awarding).
- 3.1.3. The contractor to submit work plan since all building will be operating.
- 3.1.4. The contractor to return fully filled Bill of Quantity.
- 3.1.5. The contractor to comply with EPWP projects specification.

#### 4.1. MATERIALS:

- 4.1.1 Proprietary materials where specified are to be of the brand specified or other approved by the Department.
- 4.1.2 All primers, emulsion paints, enamels, stains, varnishes, etc. are to comply with the relevant SANS specification. Paints, etc. shall be suitable for application on the surfaces to which they are being applied and those used externally shall be of exterior quality or suitable for exterior use. For any particular work the priming coat and subsequent coats of paint are to be executed with paints from the same manufacturer and in accordance with that manufacturer's instructions.
- 4.1.3 The materials are to be brought to the site in unopened containers and no adulteration will be permitted, except thinners of a quantity and quality directed by the manufacturer.
- 4.1.4 The Department shall at all times be permitted to take samples for testing purposes from open containers of any brand of paint being used on the work.
- 4.1.5 All materials, if and when required by the Department, will be subject to tests by the South African Bureau of Standards, and the cost of such tests, should the material under test not meet the requirements of this specification, shall be borne by the Contractor. Fillers and stoppings are to be suitable for use with the material being filled or stopped and to the approval of the Department.

#### 4.2. PREPARATORY WORK:

- 4.2.1 All new and existing surfaces are to be thoroughly dry and are to be cleaned of all dust, dirt, grease, oil, rust, scale, efflorescence, fungus, loose or flaking material, etc. rubbed down, stopped, filled, knotted and sanded smooth as required in accordance with the paint manufacturer's recommendations and to the approval of the Department prior to the application of paint, etc.
- 4.2.2 Asbestos cement shall be primed with an approved alkali resistant primer before the application of subsequent coats which are not, in themselves, alkali resistant.
- 4.2.3 Iron, steel and other ferrous metals shall be cleaned in accordance with SANS Code of Practice 064 to remove rust, scale, grease, oil, etc. and the surface brought to a bright metallic condition. Galvanized iron and zinc shall be cleaned in accordance with SANS Code of Practice 062 to remove the manufacturer's temporary protective coating, white rust, etc.
- 4.2.4 Other non-ferrous metals shall be thoroughly cleaned to remove all milling oils, temporary protective coatings, etc. and the surface abraded with fine water-paper and white spirit.
- 4.2.4 Woodwork to be painted shall have all knots and resinous areas treated with an approved knotting, the surface shall then be primed and all holes, etc. stopped and rubbed down smooth,
- 4.2.5 Woodwork to be oiled, stained, varnished, etc. shall be free of all stains, pencil marks and other surface discolorations and all holes, etc. stopped with tinted stopping and rubbed down smooth.
- 4.2.6 In preparing existing glazed sashes and sash doors, all loose putty is to be removed, the rebates primed and glass re-sprigged and re-puttied as necessary before the painting is commenced.

- 4.2.7 Previously distempered or lime washed surfaces to receive any other type of paint, are to have the existing distemper or lime wash completely removed by scraping or wire brushing and the surfaces treated with an approved bonding liquid.
- 4.2.8 Where existing paint film are in good condition any flaking or bared patches are to be properly feathered into the surrounding paint and spot primed as necessary.
- 4.2.9 Where existing paint films are in poor condition and require to be removed completely, they are to be removed by means of wire brushing, paint remover, burning off, or other approved method.
- 4.2.10 Paint removers shall be free of wax and caustic substances and shall preferably be of water rinse able type. When burning off paint from wood, care must be taken to avoid charring the wood.
- 4.2.11 The final state of preparatory work to existing decorated surfaces shall in all cases produce in the finished decorated surfaces a condition similar to new work.
- 4.2.12 The Contractor will be held responsible for the proper and adequate preparation of the surfaces and any work which fails to meet the manufacturer's recommendations must be made good at the Contractor's expense to the satisfaction of the Department.

### 4.3. APPLICATION OF PAINTS, ETC.

- 4.3.1 Painting may be carried out by brush, roller or spray as recommended by the manufacturer and to the approval of the Department. All paints, etc. are to be applied in strict accordance with the manufacturer's instructions. Each coat of paint is to be adequately and permanently keyed onto the previous coat or surface and shall be evenly distributed and continuous and shall dry to a smooth film, free from sags, runs or other imperfections. Each coat of paint is to be of a colour distinctive from previous or succeeding coats.
- 4.3.2 All painting must be done in accordance with a colour scheme which will be provided by the Department and rates for painting etc. are to include for all cutting in of contrasting colours and masking as required. No distinction has been made where more than one colour of the same material is required on the walls or ceiling of the same room.
- 4.3.3 Samples of colours for the final coats are to be prepared in all cases to the approval of the Department and all work must be finished to the approved colours.
- 4.3.4 Backs of wood door and similar frames and the surfaces of other new or prefixed joinery in contact with brickwork, etc. and built in as the work proceeds, shall be primed or sealed before building in to prevent moisture seeping into the wood from the mortar bedding.
- 4.3.5 Tongued and grooved and rebated edges of boards in batten doors and other such like inaccessible parts of new joinery shall, before assembly, be primed, or where the joinery is to receive a finish other than paint, be given one coat of such other finishing material.
- 4.3.6 All new external structural timbers shall be primed before the timbers are fixed in position and shall include all surfaces such as backs of fascia's and barge boards.

#### 4.4. PAINTWORK TO PREVIOUSLY PAINTED PREPARATORY WORK EXISTING SURFACES

4.4.1 All previously painted surfaces must be sanded and thoroughly washed down and allowed to dry completely before paints is applied. Blistering or peeling shall be completely removed and cracks shall be opened, filled with suitable filler and finished smooth.

4.4.2 Previously painted metal surface shall be thoroughly rubbed and cleaned down. Blistered or peeling shall be completely removed.

4.4.3 Previously painted wood surface shall be thoroughly cleaned down, Blistered or peeling paint shall be peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth.

#### 4.5. RATES:

4.5.1 Rates for painting, etc. are to include for all preparatory work, and where spraying is employed, are to include or adequately masking all surrounding areas.

4.5.2 Where diameters of pipes are stated these are the nominal internal diameters, and rates for painting pipes are to include for painting the holder bats, hangers, clips, etc. supporting the pipes.

4.5.3 Rates are to include for providing all necessary dust sheets, covers, etc. taking all necessary precautions to prevent marking the surfaces of joinery, walls, floors, glass, electrical fittings, etc. All surfaces disfigured or otherwise damaged shall be completely renovated or replaced as necessary to the approval of the Department at the Contractor's own expense.

### SCHEDULE OF RATES

#### 5. WORK TO BE DONE AND SCHEDULE OF PRICES: BENEDICTINE HOSPITAL

Item	DESCRIPTION	UNIT	QTY	RATE/ UNIT		TOTAL	
				R	c	R	c
	<p><b>NOTE:</b> All rates for items contained in this Schedule of Prices must be filled <b>excluding</b> the applicable Value Added Tax. All prices shall include labour and transport. The Administration reserves the right to Negotiate prices in the Bill of Quantities</p> <ol style="list-style-type: none"> <li>1. The contractor to provide their own water and electricity</li> <li>2. The contractor is not allowed to sleep on site</li> <li>3. The contractor is not allowed to work during the weekends</li> <li>4. All rubbles must be removed and the contractor to</li> </ol>						

	comply with OHS Act 5. The contractor to give a safety plan and work hand in hand with Hospital safety officer(This will be considered on evaluation) 6. The contractor to bring safety plan for working on height.							
<b>INSTITUTION: BENEDICTINE HOSPITAL</b>								
<b>PROPRIETARY ARTICLES:</b> All equipment and material used in this contract shall be that which is specified or other approved by SABS.								
<b>EPWP PS1</b>								
1.	The contractor to comply with EPWP projects specification.	Each						
<b>EYE CLINIC (Inside painting) PS2</b>								
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m <sup>2</sup>	72					
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m <sup>2</sup>	72					
3.	Supply and install 1.2m steel door frame protectors	01	01					
4.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01					
<b>WAITING AREA FOR EYE CLINIC (Inside painting) PS3</b>								
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m <sup>2</sup>	114					
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m <sup>2</sup>	114					
3.	Also prepare and painting of ceiling board with SABS Approved PVA.	m <sup>2</sup>	70					
3.	Repair and replace of damaged rhino board wall also replace 30mm x 30mm steal corner wall protector. Skimming is also required for the surface to look good and clean.	m <sup>2</sup>	05					
4.	Replace commercial blank door with 2 lever union mortise lock and paint to match all existing doors	01	01					
6.	Supply and install of plywood boards inside and outside all consulting rooms 1.200m high to prevent any damage from chair users and trolleys. The contractor to make means of mounting both boards in terms of screws/bolt and nuts to be firm and look nice. Top edge and the corner to mould by using router machine. Also be painted	m <sup>2</sup>	30					



7.	Supply and install 1.2m steel door frame protectors	01	01				
8.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>ROOM 15 (Inside painting) PS4</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m <sup>2</sup>	36				
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m <sup>2</sup>	36				
3.	Also prepare and painting of ceiling board with SABS Approved PVA.	m <sup>2</sup>	09				
4.	Replace commercial blank door with 2 lever union mortise lock and paint to match all existing doors	01	01				
5.	Supply and install 1.2m steel door frame protectors	01	01				
6.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>ROOM 14 (Inside painting) PS5</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m <sup>2</sup>	49				
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m <sup>2</sup>	49				
3.	Also prepare and painting of ceiling board with SABS Approved PVA.	m <sup>2</sup>	12				
4.	Replace commercial blank door with 2 lever union mortise lock and paint to match all existing doors	01	01				
5.	Supply and install 1.2m steel door frame protectors	01	01				
6.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>PASSAGE BETWEEN 13 AND 14 (Inside painting) PS6</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m <sup>2</sup>	24				
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m <sup>2</sup>	24				
3.	Also prepare and painting of ceiling board with SABS Approved PVA.	m <sup>2</sup>	03				
5.	Supply and install 1.2m steel door frame protectors	01	01				

6.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>ROOM 13 (Inside painting) PS7</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m <sup>2</sup>	36				
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m <sup>2</sup>	36				
3.	Also prepare and painting of ceiling board with SABS Approved PVA.	m <sup>2</sup>	09				
4.	Replace commercial blank door with 2 lever union mortise lock and paint to match all existing doors	01	01				
5.	Supply and install 1.2m steel door frame protectors	01	01				
6.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>WAITING AREA FOR ROOM 10,11 and 12 (Inside painting) PS8</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m <sup>2</sup>	99				
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m <sup>2</sup>	99				
3.	Also prepare and painting of ceiling board with SABS Approved PVA.	m <sup>2</sup>	44				
4.	Supply and install of plywood boards inside and outside all consulting rooms 1.200m high to prevent any damage from chair users and trolleys. The contractor to make means of mounting both boards in terms of screws/bolt and nuts to be firm and look nice. Top edge and the corner to mould by using router machine. Also be painted	m <sup>2</sup>	30				
5.	Supply and install 1.2m steel door frame protectors	01	01				
6.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>ROOM 12 (Inside painting) PS9</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m <sup>2</sup>	42				
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m <sup>2</sup>	42				
3.	Also prepare and painting of ceiling board with SABS Approved PVA.	m <sup>2</sup>	09				

4.	Replace commercial blank door and Mirant frame with 2 lever union mortise lock and paint to match all existing doors	01	01				
5.	Supply and install 1.2m steel door frame protectors	01	01				
6.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>ROOM 11 (Inside painting) PS10</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m <sup>2</sup>	42				
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault	m <sup>2</sup>	42				
3.	Also prepare and painting of ceiling board with SABS Approved PVA.	m <sup>2</sup>	09				
5.	Supply and install 1.2m steel door frame protectors	01	01				
6.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>ROOM 10 (Inside painting) PS11</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m <sup>2</sup>	42				
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault	m <sup>2</sup>	42				
3.	Also prepare and painting of ceiling board with SABS Approved PVA.	m <sup>2</sup>	09				
5.	Supply and install 1.2m steel door frame protectors	01	01				
<b>OPDPASSAGE (Inside painting and floor vinyl sheet replacement) PS12</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m <sup>2</sup>	469				
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m <sup>2</sup>	469				
3.	Also prepare and painting of ceiling board with SABS Approved PVA.	m <sup>2</sup>	67				
4.	Painting of wooden bumper rails with clear varnish paint.	m <sup>2</sup>	26				
5.	Painting of wooden bumper rails with clear varnish paint. Remove and replace of						
5.	Supply and install 1.2m steel door frame protectors	01	01				

6.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>REPLACE VINYL FLOOR SHEET IN OPD PASSAGE AND SKIRTING PS13</b>							
1.	<p><b>PROCESS</b> Remove all existing skirting and vinyl sheeting, the contractor shall carefully clean up the place and floors must be clean and free of obstacles before starting to work.</p> <p><b>LAYING:</b> All floor coverings and skirting to be laid by workmen experienced in laying the particular type of floor covering. In strict accordance with the instructions issued by the Manufacturer of the materials being used.</p> <p>All adhesive must be the correct adhesives as supplied or recommended by the manufacturer of the material being used.</p> <p>Floor sheeting : Supply and fix 2.0/2.5mm thick 1.2m wide Marley Super flex fully flexible vinyl floor sheeting manufactured to SABS Specification.</p> <p><b>ADHESIVE :</b> Use Marley No 60 Acrylic Adhesive spread with notched trowel having 1.5mm x 1.5mm x 1.5mm triangular notches at 4.0mm centers at the rate of between 5.5m<sup>2</sup> and 6.5m<sup>2</sup></p> <p><b>WELDING RODS:</b> Welded sheet flooring is to have the seams welded together by approved process to form the seamless floor or lining. Patterned sheet floorings are to be matched at joints. Vinyl skirting and edging strips are to be fully bonded to the backing surfaces. Marley Super flex may, 24hours after installation be welded using Marley Welding Rod.</p> <p><b>POLISHING:</b> The newly laid floor should after 72hours are scrubbed with diluted neutral detergent complying with SABS825 and thoroughly rinsed. Three coats of a water based floor dressing complying with SABS 1042.</p>	m <sup>2</sup>	162				
<b>X-RAY No. 1 PS14</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m <sup>2</sup>	42				
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m <sup>2</sup>	42				
3.	Also prepare and painting of ceiling board with SABS	m <sup>2</sup>	12				

	Approved PVA.						
4.	Painting of door	01	01				
5.	Supply and install 1.2m steel door frame protectors	01	01				
6.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>X-RAY No. 2 PS15</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m2	42				
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m2	42				
3.	Also prepare and painting of ceiling board with SABS Approved PVA.	m2	12				
4.	Painting of door	01	01				
5.	Supply and install 1.2m steel door frame protectors	01	01				
6.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>X-RAY Manager 's office PS16</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m2	48				
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m2	48				
3.	Also prepare and painting of ceiling board with SABS Approved PVA.	m2	16				
4.	Painting of door	01	01				
5.	Supply and install 1.2m steel door frame protectors	01	01				
6.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>Occupational nurse office PS17</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m2	42				
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m2	42				
3.	Also prepare and painting of ceiling board with SABS Approved PVA.	m2	12				

4.	Painting of door	01	01				
5.	Supply and install 1.2m steel door frame protectors	01	01				
6.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>OPD Manager 's office PS18</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m2	42				
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m2	42				
3.	Also prepare and painting of ceiling board with SABS Approved PVA.	m2	12				
4.	Painting of door	01	01				
5.	Supply and install 1.2m steel door frame protectors	01	01				
6.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>OPD Kitchen PS19</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m2	42				
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m2	42				
3.	Also prepare and painting of ceiling board with SABS Approved PVA.	m2	12				
4.	Paintings of door also replace 2 lever mortise locker.	01	01				
5.	Supply and install 1.2m steel door frame protectors	01	01				
6.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>OPD Toilet PS20</b>							
1.	Replace abnormal frames 110mm thick and doors (both Mirant) and 2 lever union mortise locks also paint them.	02	02				
3.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m2	10				
3.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m2	10				

4.	Also prepare and painting of ceiling board with SABS Approved PVA.	m2	20				
5.	Replacing of paraplegic toilet (Vaal)	01	01				
6.	Replacing of wash hand basin(Vaal) with separated cobra elbow action taps	01	01				
5.	Supply and install 1.2m steel door frame protectors	01	01				
6.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>ROOM 05 (Inside painting) PS21</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m <sup>2</sup>	42				
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m <sup>2</sup>	42				
3.	Also prepare and painting of ceiling board with SABS Approved PVA.	m <sup>2</sup>	12				
4.	Replace abnormal frame 110mm thick and door (both Mirant) and 2 lever union mortise lock also paint.	01	01				
5.	Supply and install 1.2m steel door frame protectors	01	01				
6.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>STAFF TOILET (Inside painting) PS22</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m <sup>2</sup>	03				
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m <sup>2</sup>	03				
3.	Also prepare and painting of ceiling board with SABS Approved PVA.	m <sup>2</sup>	2,5				
4.	Also paint door.	01	01				
5.	Supply and install 1.2m steel door frame protectors	01	01				
6.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>ROOM 04 (Inside painting) PS23</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m <sup>2</sup>	52				

2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m <sup>2</sup>	52				
3.	Also prepare and painting of ceiling board with SABS Approved PVA.	m <sup>2</sup>	13				
4.	Replace abnormal only the door (Mirant) with 2 lever union mortise lock also paints.	01	01				
5.	Supply and install 1.2m steel door frame protectors	01	01				
6.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>ROOM 03 (Inside painting) PS24</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m <sup>2</sup>	56				
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m <sup>2</sup>	56				
3.	Also prepare and painting of ceiling board with SABS Approved PVA.	m <sup>2</sup>	16				
4.	Replace abnormal only the door (Mirant) with 2 lever union mortise lock also paints.	01	01				
5.	Supply and install 1.2m steel door frame protectors	01	01				
6.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>ROOM 02 (Inside painting) PS25</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m <sup>2</sup>	56				
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m <sup>2</sup>	56				
3.	Also prepare and painting of ceiling board with SABS Approved PVA.	m <sup>2</sup>	16				
4.	Replace abnormal frame and the door (both Mirant) with 2 lever union mortise lock also paints.	01	01				
5.	Supply and install 1.2m steel door frame protectors	01	01				
6.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>ROOM 06 (Inside painting) PS26</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m <sup>2</sup>	56				



2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m <sup>2</sup>	56				
3.	Also prepare and painting of ceiling board with SABS Approved PVA.	m <sup>2</sup>	16				
4.	Replace abnormal frame and the door (both Mirant) with 2 lever union mortise lock also paints.	01	01				
5.	Supply and install 1.2m steel door frame protectors	01	01				
6.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>ROOM 01 (Inside painting) PS27</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m <sup>2</sup>	49				
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m <sup>2</sup>	49				
3.	Also prepare and painting of ceiling board with SABS Approved PVA.	m <sup>2</sup>	16				
4.	Supply and install 1.2m steel door frame protectors	01	01				
5.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				
<b>MAIN ENTRANCE DOOR PS28</b>							
1.	Replace Main Hospital Entrance <ul style="list-style-type: none"> <li>➤ Size 1800 x 2032 x 40 with safety glazing viewing panel on both sides.</li> <li>➤ Locks, barrel bolts, floor springs and hinges. Dead lock with escutcheons, flush barrel bolts to one leaf, 1 pair double action floor spring.</li> <li>➤ Handles, 2 pairs of pull handles.</li> <li>➤ Door stops, adjustable grout-in</li> <li>➤ Kick and push plates are required on the door (cladding grade 304stainless steel)</li> </ul>	01	01				
<b>NEW ERMEGENCY ROOM PS29</b>							
1.	Prepare wall also supply and paint sure coat white undercoat SUC1.	m <sup>2</sup>	70				
2.	Supply and paint 2 coats for Cashmere 15 years product guarantee B2-2 Ocean Sault.	m <sup>2</sup>	70				
3.	Also prepare and painting of ceiling board with SABS	m <sup>2</sup>	25				

	Approved PVA.						
4.	Replace abnormal frame and the door (both Mirant) with 2 lever union mortise lock also paints.	01	01				
5.	Supply and install 1.2m steel door frame protectors	01	01				
6.	Kick and push plates are required on the door (cladding grade 304stainless steel)	01	01				

**COLLECTION SUMMARY**

**INSTITUTION: BENEDICTINE HOSPITAL**

**PROJECT: OPD PASSAGE AND CONSULTING ROOMS WALL PAINTING AND FLOOR VINYL SHEET REPLACEMENT ON THE PASSAGE ALSO REPLACEMENT OF MIRANTI FRAME AND DOORS.**

**NOTE:**

**THIS COLLECTION SUMMARY MUST BE COMPLETED IN FULL BY THE CONTRACTOR AND RETURNED TOGETHER WITH THE TENDER FORM.**

Collection Summary	PS 1	R		
Collection Summary	PS 2	R		
Collection Summary	PS 3	R		
Collection Summary	PS 4	R		
Collection Summary	PS 5	R		
Collection Summary	PS 6	R		
Collection Summary	PS 7	R		
Collection Summary	PS 8	R		
Collection Summary	PS 9	R		
Collection Summary	PS 10	R		
Collection Summary	PS 5	R		
Collection Summary	PS 11	R		
Collection Summary	PS 12	R		
Collection Summary	PS 13	R		
Collection Summary	PS 14	R		
Collection Summary	PS 15	R		
Collection Summary	PS 16	R		

Collection Summary	PS 17	R		
Collection Summary	PS 18	R		
Collection Summary	PS 19	R		
Collection Summary	PS 20	R		
Collection Summary	PS 21	R		
Collection Summary	PS 22	R		
Collection Summary	PS 23	R		
Collection Summary	PS 24	R		
Collection Summary	PS 25	R		
Collection Summary	PS 26	R		
Collection Summary	PS 27	R		
Collection Summary	PS 28	R		
Collection Summary	PS 29	R		
SUB-TOTAL		R		
ADD Provision for Value Added Tax Allow 15% of SUB-TOTAL				
<b><u>TOTAL: CARRIED TO FORM</u></b>		R		