



Quotation Advert

Opening Date: 2020-02-26
 Closing Date: 2020-03-06
 Closing Time: 11:00

INSTITUTION DETAILS

Institution Name: Manguzi hospital
 Province: KwaZulu-Natal
 Department or Entity: Department of Health
 Division or section: Central Supply Chain Management
 Place where goods / services is required: MAIN KITCHEN
 Date Submitted: 2020-02-25

ITEM CATEGORY AND DETAILS

Quotation Number: ZNQ: 689/19/20
 Item Category: Services
 Item Description: RENOVATIONS TO THE MAIN KITCHEN
REQUIREMENTS:
 - CIDB
 - GB GRADE
 - EB GRADE
 - LETTER OF GOOD STANDING
 Quantity (if supplies): 01

COMPULSORY BRIEFING SESSION / SITE VISIT

Select Type: Compulsory Site Visit
 Date: 2020-03-03
 Time: 10H00
 Venue: MANGUZI HOSPITAL

QUOTES CAN BE COLLECTED FROM: SITE VISIT

QUOTES SHOULD BE DELIVERED TO: TENDER BOX/ VIA EMAIL: andile.gumede@kznhealth.gov.za

ENQUIRIES REGARDING THE ADVERT MAY BE DIRECTED TO:



Name: THEMBA MAPHUMULO
Email: andile.gumede@kznhealth.gov.za
Contact Number: 035 5920 150 EXT 212
Finance Manager Name: FS MPANZA
Finance Manager Signature: 

No late quotes will be considered



DIRECTORATE: MAINTENANCE

Physical Address : Manguzi Main Road ,KwaNgwanase
 Postal Address : Private Bag X301 ,KwaNgwanase ,3973
 Tel: 035 5920 150 Fax: 035 5920 158 Email: Sizwe.Mavundla@kznhealth.gov.za
www.kznhealth.gov.za

02/08/2019

Specification for renovation at main kitchen

- The contractor is requested to take instruction from maintenance foreman or Artisan chief.
- It is the responsibility of the contractor to ensure health and safety.
- Screening protection on working area is required.
- Kitchen services will be on progress during construction process
- Contractor will request to make arrangement for construction daily to ensure kitchen process is not disturbed.
- Dust flowing all over will not be accepted
- Any damage during construction process contractor is liable for repair and replacement
- Hospital is not responsible for any injury ,loss or theft on site
- Constructor is requested to use SABS approved material
- All general labor must EPWP
- Provide a credited people to install suspended ceiling installer.
- Suspended Ceiling give proof of previous installation
- Contractor must be registered with CIDB GB\$EB grade
- Provide certificate for completion on suspended ceiling installation
- All electrical installation must be done by qualified electrician and provide compliance certificate in completion of work.
- Industrial wall mounted fan must have isolation taken from the existing ceiling fan
- Fan mounted at 2 meter high above from the round , surface wiring to be used 2,5 mm round cable 2 core
- Lights fitting comes with 1,50mm
- Round flexible cable 2 meter with 5 amp plug top.
- Provide brick layer certificate for a tile installer.
- No sleeping allowed on site.

<u>Material to be used</u>	QUANTITY	AMOUNT
1.Striping of floor tile	374 m	
2.Striping of wall tile	149 m	
3.Striping of suspended ceiling	395 m	
4.Installation of floor tile 300mm X 300mm GN 537 granite floor tile	414 m	
5.Installation of wall tile Jonson & Jonson 100mm X	414 m	

100 mm		
6.Installation of suspended ceiling	395 m	
7.Installation of louver 1.2 mm x 600mm	14	
8.Replacement of 1.2 mm x 600 mm of florescent light fitting	50	
9.Industrial wall mounted fan	6	
10.Antibacterial grout SABS approved		
11. Tile cement		
12.spacer		
13.Painting of walls with kitchen and toilet painter	125 m	
14.Under coat paint white	125 m	
15. EWP labor	5	
16. 20 Amp isolator.	6	
17. round surface cable 2core	50meter	
18. 16x16mmx3meter PVC trucking	3	
Total Amount		R