




SharePoint		Khanyile Thulani + ?
 KWAZULU-NATAL PROVINCE HEALTH REPUBLIC OF SOUTH AFRICA		
KZN Health Intranet		
Search this site <input type="text"/>		
HOME CORPORATE INFORMATION COMPONENTS DIRECTORY DISTRICT OFFICES HEALTH FACILITIES		
KZN Health > Components > Supply Chain Management		
AdvertQuote		
 KWAZULU-NATAL PROVINCE HEALTH REPUBLIC OF SOUTH AFRICA		
Quotation Advert		
Opening Date:	2021-10-27	<input type="text"/>
Closing Date:	2021-11-15	<input type="text"/>
Closing Time:	11:00	
INSTITUTION DETAILS		
Institution Name:	Mosvold hospital	<input type="text"/>
Province:	KwaZulu-Natal	
Department or Entity:	Department of Health	
Division or section:	Central Supply Chain Management	
Place where goods / services is required	MOSVOLD HOSPITAL	
Date Submitted	2021-10-28	<input type="text"/>
ITEM CATEGORY AND DETAILS		
Quotation Number:	ZNQ: ZNQ / MVH / 351 / 22	
Item Category:	Services	<input type="text"/>
Item Description:	REPAIR (REPLACEMENT OF PERMETER LIGHT) AND INSTALLATION OF NEW LIGHTS WHERE NEEDED AT MOSVOLD HOSPITAL (SPEC ATTACHED)	
Quantity (if supplies)	054	
COMPULSORY BRIEFING SESSION / SITE VISIT		
Select Type:	Compulsory Briefing Session	<input type="text"/>
Date :	02-08 NOVEMBER 2021	<input type="text"/>
Time:	9H00 AM	
Venue:	MOSVOLD HOSPITAL	
QUOTES CAN BE COLLECTED FROM:	QUOTATION DOCUMENTS WILL BE COLLECTED DURING THE SITE VISIT	
QUOTES SHOULD BE DELIVERED TO:	MOSVOLD TENDER BOX OR BY EMAIL	
ENQUIRIES REGARDING THE ADVERT MAY BE DIRECTED TO:		
Name:	TG. KHANYILE	
Email:	thulani.khanyile@kznhealth.gov.za	
Contact Number:	035 5910145 EXT.153	

Finance Manager Name:

MRS NP MYENI

Finance Manager Signature:



No late quotes will be considered

MOSVOLD HOSPITAL
ASSISTANT DIRECTOR: FINANCE

2021 -10- 26

INGWAVUMA MAIN ROAD
PRIVATE BAG X2241, INGWAVUMA, 3968
TEL: 035 591 0122 FAX: 035 591 0039/148



health

Department:
Health
PROVINCE OF KWAZULU-NATAL

DIRECTORATE: Mosvold District Hospital

Physical Address: Ingwavuma Main Road
Postal Address: Private Bag X 2211, Ingwavuma, 3968
Tel: (035)59101222 Fax: (035)55910148 Email:
www.kznhealth.gov.za

Mr. J Mingomezulu

SPECIFICATION FOR REPLACEMENT OF PERIMETER LIGHTS AT MOSVOLD HOSPITAL

CONTRACTOR REQUIREMENTS

1. Companies must be valid registration with CIDB minimum 1EB or 1EP
2. Companies must comply with CSD
3. Companies must have valid letter of good standing from the Department of Labor
4. Companies must be registered as an electrical company with electrical board proof to attach
5. The company must have valid liability insurance of ~~R3000 000~~ ^{R3 000} proof to attach

NB This project must be finish within 6 weeks after site handed over to the company

Contractor's directions:

The company must notice maintenance manager prior project commencement so that all arrangement is done with relevant section manager.

The company must sign the contractor's project agreement.

The company will be required to submit project plan before this project starts

Receive sign site completion when then project is finished

This project must be finished within 6 weeks

Replacement location:

Middle 23x lights repair

Main gate to left and right driveway 27(new)

Government vehicles 2x flood light new (back and front)

Behind chronic park home 1x light (new)

Behind elevated concrete tank x1(new)

Scope of work

Test and trace the lights from kiosk (by maintenance all walkway)

All lights must be supplied from kiosk_K3 with its own 15A circuit breaker

Replace all cables that are found to be faulty

All new placed cable must be 10mm 3core armored cable (single phase)

The cable must be at barred at 500mm underground on top of sand (to prevent cable damage)

The company must mark the cable for easy identification (marker)

The company must make a schematic drawing of the installation that will be submitted to project manager office

Poles used must be aluminum at the middle of hospital and at the back of hospital the company must use treated 9m 180-210mm pole top diameter treated poles with eskom specification of treated, aluminum poles must be existing type of aluminum, this aluminum poles must be 2.5m above the ground being barred at 500mm and treated poles should be barred at 1.5m holes for planting 9m poles

All poles must be secured with mixed of sand, stone and cement 2:2:1

All poles must have 5A breaker each installed on coverable opening at 1m above the ground

All lights must be automatic operated with a day light switch x3 and each switch must be connected via contactor x3 (Current rating : 18A (AC3) or 32A (AC1))

Maximum voltage : 220/230V AC coil, 3 pole 50/60HZ x 69.5VA (pull-in), 4-7.2VA (sealing)


Main contacts: 3 (NO)

BOQ

Description	Size	quantity	Unity price	Total price
Armored 3core cable	10mm			
Sand	River sand			
Stone	19mm			
Cement	42.5N			
Maker		7		
Aluminum poles	3m			
Treated poles with 180-210mm pole top diameter treated poles with eskom specification of treatment	9m	4		
Breaker	5A	27		
Breaker	15A	3		
Day light switch		3		
contactor		3		
Lights repairs		23		
Area lights fitting post top complete with switch gear and lamps IP65 125W				
Security lights IP65 400W cool white light fittings complete with switch gear and lamps				
Supply and install 4way brackets to be installed on top of 9m pole to install two back to back lights fittings				
Test and do load balancing on lighting circuit you were working on				
Test and issue a compliance certificate				

• KINDLY RETURN ALL DOCUMENTATION WHEN REPLYING

Compiled by
J Mngomezulu

Sign  date 19/8/2021
Artisan

• KINDLY RETURN ALL DOCUMENTATION WHEN REPLYING