

SharePoint

Hlatshwayo Petros



## KZN Health Intranet

KZN HEALTH

Search this site

[HOME](#) [CORPORATE INFORMATION](#) [COMPONENTS](#) [DIRECTORY](#) [DISTRICT OFFICES](#) [HEALTH FACILITIES](#)

KZN Health &gt; Components &gt; Supply Chain Management

AdvertQuote



## Quotation Advert

Opening Date: ~~2022-11-15~~ 25-11-2022

Closing Date: ~~2022-11-25~~ 06-12-2022

Closing Time: 11:00

## INSTITUTION DETAILS

Institution Name: Manguzi hospital

Province: KwaZulu-Natal

Department or Entity: Department of Health

Division or section: Central Supply Chain Management

Place where goods / services is required: MANGUZI HOSPITAL

Date Submitted: 2022-11-15

## ITEM CATEGORY AND DETAILS

Quotation Number: ZNQ: MZH-663-22-23

Item Category: Services

Item Description: RENOVATION OF THERAPY UNIT BUILDING

Quantity (if supplies): ONCE

## COMPULSORY BRIEFING SESSION / SITE VISIT

Select Type: Compulsory Site Visit

Date: ~~2022-11-18~~ 29-11-2022

Time: 11H00

Venue: MANGUZI HOSPITAL DINNING HALL

QUOTES CAN BE COLLECTED FROM: QUOTE WILL COLLECTED ON THE SITE MEETING

QUOTES SHOULD BE DELIVERED TO: TENDER BOX AT MAIN GATE OR VIA EMAIL

## ENQUIRIES REGARDING THE ADVERT MAY BE DIRECTED TO:

Name: PETROS HLATSHWAYO

Email: petros.hlatshwayo@kznhealth.gov.za

Contact Number: 0355920150

Finance Manager Name:

C. NHLEKO

Finance Manager Signature:

No late quotes will be considered

PROVINCE OF KWAZULU-NATAL  
DEPARTMENT OF HEALTH

CONTRACT No. ZNT

**MAINTENANCE, SERVICING, REPAIR, UPGRADING, REPLACEMENT AND MINOR NEW WORKS FOR STRUCTURAL WORK AT ALL KWAZULU-NATAL PROVINCIAL HEALTH FACILITIES**

**BILLS OF QUANTITIES**

**SCHEDULED RATES**

Item	Description	Qty	Supply rate	Install rate	Sub total	Total
	<b>Supply and install food macerator.</b>  Tender to be aware that the hospital is fully functional and that service can not be interrupted so due allowance must be made in this regard. The quotation shall include all costs involve. The contractor is required to upgrade an existing toilet to accommodate people living with disability by closing one toilet demolish the partitioning wall.					
1	Stripping of roofing slate tiles of	262m <sup>2</sup>				
2	Stripping of 38x38 mm binderies	262m <sup>2</sup>				
3	Installation of 2x3. Treated wood purlin	262m <sup>2</sup>				
4	Installation of chromadek sheeting self-clipping	262m <sup>2</sup>				
5	Stripping of walls	273m <sup>2</sup>				
6	Nu-Tec installation 12mm	273m <sup>2</sup>				
7	Aluminum strip angle shape 50mmx50mm	130m				
8	8mm self-tapping screws galvanized type 15mm long.	1000				
9	Tilling of floors GN578 8mmx330x330mm	262m <sup>2</sup>				
10	Ridden of	50m				
11	Aluminum Valley sheeting of	30m				
12	Facial board	30m				
13	Budge board	64m				
14	Socket outlet	16				
15	Hand wash basin recommended vaal medical type	02				
16	Toilet Vaal and shire cistern lockable for people living with disability.	01				
17	Painting of wall's with warm cream paint water proofing.	300m <sup>2</sup>				
18	Wall partitioning of 1.3x3x2height 12mm nu-Tec	11m				
19	Replace ceiling 7x4m and 8x4m	60m <sup>2</sup>				
20	Ceiling paint	60m <sup>2</sup>				
21	Tile cement	300m <sup>2</sup>				
22	Grout	50m <sup>2</sup>				
23	Stainless steel hand rail	03				



