

| | |
|--------|--|
| | Amendments for Site Briefing: 23 August 2022 |
| | ZNB 5026/2022-H |
| | |
| | <u>CMRL</u> |
| 2.3.32 | Respray existing panels at existing 315kVA generator, RED, indicating essential supply |
| 2.3.33 | Rewire existing gen panel; such that all DBs are fed from main incomer and generator and placed onto Essential supply from new genset. |
| 2.3.34 | Installation of Breaker panel: |
| | Supply, deliver and install suitably rated circuit breakers (2 off) and suitably rated panel (1 off) for cable protection to be installed within main incomer plant room and installed in accordance with SANS standards (SANS 10142 I&II) |
| | |
| | <u>KZNCL</u> |
| 2.3.32 | Installation of Breaker panel: |
| | Supply, deliver and install suitably rated circuit breakers (2 off) and suitably rated panel (1 off) for cable protection to be installed within main incomer plant room and installed in accordance with SANS standards (SANS 10142 I&II) |
| | |
| | <u>General</u> |
| | The specification regarding the batteries shall be Delco/Deltec type with a minimum warranty of 2 years. |
| | The canopies manufactured and supplied to the laundries shall be weatherproof and not tropical. Which ensures there is no water/moisture ingress into the interior compartment of the genset from weatherside louvres. |