

ZNB 5026/2022-H – AMENDMENTS AND NOTES

1. BOTH INSTALLATIONS TO ENSURES **72 HOURS STANDBY AT 100% LOAD**
2. CIDB 6EP **OR** 6EB
3. CONTRACT DURATION: 9 MONTHS
4. BOTH GENERATORS, INCLUDING CANOPY, BASE FRAME, BASE TANK AND BULK TANK TO BE CONSTRUCTED WITH 3CR12 MATERIAL
5. BASE TANK MINIMUM CAPACITY OF 1000L
6. NOTE: DEEP CYCLE LITHIUM IRON BATTERIES WITH MINIMUM WARRANTY OF 10 YEARS
7. IT WOULD BE BENEFICIAL (NOT COMPULSORY) TO PROVIDE RATES FOR A THIRD SERVICE DUE TO THE HIGH INCIDENCE OF LOAD SHEDDING. DO NOT INCLUDE IN THE PRICE MERELY HIGHLIGHT THE ESTIMATED COSTS SUCH THAT IT IS EASIER TO BDUGET FOR IF A VO IS REQUIRED.
8. TREE AND FOLIAGE REMOVAL IS THE COST OF THE CONTRACTOR AND TO BE INCLUDED IN CIVIL/BUILDING WORKS.