KWAZULU-NATAL PROVINCE
HEALTH
REPUBLIC OF SOUTH AFRICA

Quotation Advert

Opening Date: 02/10/2026
Closing Date: 16/10/2026

Closing Time: 11:00

INSTITUTION DETAILS
Institution Name: Othobothini CHC

Province: KwaZulu-Natal

Department of entity: Department of Health

Division or section: Supply Chain Management

Place where goods/ 3969 **Othobothini CHC D850 Road next to Msiyane High School, Jozini**

Service is required:

Date Submitted: **02/10/2026**

ITEM CATEGORY AND DETAILS

Quotation number: **ZNQ: OTH/149/26-27**

Item Category: Services

Item Description: SUPPLY, DELIVER AND INSTALL ELECTRICAL MATERIALS, AIR CONDITIONER AND STEEL HAND WASH

COMPULSORY BRIEFING SESSION / SITE VISIT

Select Type: Complusory Briefing

Time: **11:00 am**

Venue: **Othobothini CHC, Lecture Hall**

DATE: **09/10/2026**

Requirements: **CIDB GRADE: 1ME OR ABOVE**

- **Letter of good standing in electrical**
- **Trade test of electrical/ Diploma/degree/any qualification in electrical.**
- **SARACA certificate**
- **3 X Completion certificate or 3 x traceable completion letters for similar work (installation of air conditioners)**
- **Refrigeration Gas Card**

QUOTES CAN BE COLLECTED FROM: Othobothini CHC during briefing

QUOTE SHOULD BE DELIVERED TO: OTHOBOTHINI CHC, QUOTATION BOX

ENQUIRIES REGARDING ADVERT MAY BE DIRECTED TO:

Name: Miss C.F KHUMALO

Email: othobothini.quotations@gmail.com

Contact number: 035 572 9002

Finance Manager Name: Ms N.P DUBE

Finance Manager signature: _____

KWAZULU-NATAL PROVINCE
HEALTH
REPUBLIC OF SOUTH AFRICA

DIRECTORATE:

OTHOBOTHINI CHC
D850 Road, Next To Msiyane High School, Private Bag X012, Jozini 3969
eMail:Othobothini.Maintenance@kznhealth.gov.za
Tel.: 035 572 9002, Fax: 035 572 9082.
www.kznhealth.gov.za

SYSTEMS

Enquiries: Ms P.S. Phakathi
Telephone no. 035 572 9002

SCOPE OF WORK FOR INSTALLATION

A comprehensive installation typically includes:

- **Air conditioners:**
- **Removal:**
  -Removal of Three 12btu air conditioner from 1.Small admin kitchen, 2.Two from Flue clinic. Please close the holes with **Cream Rhino Lite** and leave the wall smooth and clean.
  Install:
  To be installed in the following areas:
  1. Acute room 4
  2. Acute Rehabilitation room
  3. Dietician Stores.

- **New installation of Air Conditioner:**
  -One 24btu air conditioner will be installed on SCM Storage Container.
  -Two 24btu air conditioner will be installed on Record Storage Container.
  All air conditioner must be connected to **isolator with each 20A CBI breaker with 2.5 mm^2 core electric wire.**
  20mm^2 drain PVC Pipe

- **Washing basin:**
  -One Washing basin will be installed on SCM Storage Container.
  - One Washing basin will be installed on Record Storage Container.
  -Basin must be mounted securely with bolt and nut on the container outside near the entrance door.
  -The **15mm polycopper** pipe must be used for the supply of water and valve to be installed for isolation.
  -The waste pipe of the sink must be **50mm diameter.**
  -The waste pipe must be fitted and you have to dig the trench **of 300mm deep x 50mm wide** in the ground to the near gully.
  -Water Supply will be taken from PHC building, where area is concrete the pipe must be secured with **angle iron.**

- **Distribution Board:**
  Designed for 12-way circuit breaker must be securely mounted on the wall of container by using bolt and nut. The D.B must have **2x 2pole Main breaker, 2xEarth leakage, 6x20A breaker and 4x10A breakers (All CBI).**

- **Lights:**
  -Fluorescent lights will be installed inside the container on the roof.
  -Flood lights will be installed outside the container and surroundings areas for clear view at night.

- **Plug points:** 2x 16A plug points will be installed inside, in each container.

- **Armoured cable**: Electrical Supply will be taken from PHC building; you have to dig the trench of **300mm deep x 50mm wide** in the ground from outside of the PHC building to the 1st container and the 2nd container. Where area is concrete you will open the trench and close it and leave the area as it was.

- **Compliance:** Please provide us with **COC** for electricity.

NB:

1. The work to be carried out in terms of this section of the project comprises the supply and installation of all the materials necessary, as per the Bill of Quantities.
2. All work will be checked and approved by the Chief works Inspector/Artisan foreman.
3. All workmanship will be done fully in accordance of the Occupational Health and Safety act 85/1993, as amended.
4. Site to be cleared daily of building rubble and work area always kept clean **(HOUSEKEEPING).**
5. Lead time of 1 Week allows contractor to obtain material and spares, Lead time will officially begin only once **SITE HANDOVER CERTIFICATE** is awarded.
6. Before handing over the Completion Certificate:
   - The site will be inspected.
   - Contractor will provide us with Electrical COC.
7. After the above mention you will able to supply us with the invoice.

PLEASE NOTE THAT THIS CONTRACT PERIOD IS FOUR (4) WEEKS.